




GRID LOCATION	
G/3	D/1-5



NOTA:

Gaurile sunt cu 2mm mai mari decat diametrul buloanelor;  
Lungimea cordoanelor de sudura este egala cu conturul de suprapunere a pieselor.  
Grosimea sudurilor va fi egala 0.7tmin; dar nu mai putin de 3mm.

EXTRAS MATERIALE PTR 1 ANSAMBLU				G/3	1	buc. necesare
Positia	Dimensiunea	Otel	buc.	Lungime [mm]	Aria laterala [mp]	Greutate [kg]
1001	PL10*70	S235JR	4	100	0	0
1002	PL3*80	S235JR	2	80	0	0
1004	PL8*80	S235JR	4	130	0	1
1008	PL10*130	S235JR	4	261	0	1
1009	PL10*133	S235JR	4	182	0	1
1012	60*8	S235JR	8	140	0	1
P/1	RHS80*4	S235JR	1	9050	3	86
P/2	RHS80*4	S235JR	2	4743	1	44
P/3	RHS50*4	S235JR	1	1336	0	8
P/4	RHS50*4	S235JR	2	886	0	5
P/5	RHS50*4	S235JR	2	428	0	2
P/6	RHS50*4	S235JR	2	1610	0	9
P/7	RHS50*4	S235JR	2	1323	0	8
P/8	PL10*70	S235JR	4	200	0	1
P/10	RHS80*4	S235JR	1	290	0	3
				Total	9	257

Verificator					
Verificator/ Expert	Nume	Semnatura	Cerinta	REFERAT / EXPERTIZA / NR. / DATA	
<p align="center"><b>S.C. A.G. PROIECT-S S.R.L.</b>  C.U.I. 17069804 , J02/2218/2004  B_dul. Stefan Augustin Dolnas, nr. 41. ap. 2, ARAD  Tel: 0721740641</p>				<u>Beneficiar:</u> <b>COMUNA ZERIND</b> prin Primar Simandi Alexandru	Proiect nr.: 08/2022
SPECIFICATIE	NUME	SEMNATURA	SCARA	<u>Titlu proiect:</u>	Faza:
SEF PROIECT:	Arh. Popa Romeo		1:5	ETAJARE CLADIRE VESTIARE BAZA SPORTIVA Jud. Arad, Comuna ZERIND, satul ZERIND, CF 302562	DTAC + PT
Proiectat:	Ing. Molnar Huba		DATA	<u>Titlul plansei:</u>	Plansa nr.
Desenat:	Ing. Molnar Huba		2022	GRINDA DE ZABRELE G/3	M.11