




GRID LOCATION	
G/5	F/1-5



NOTA:

Gaurile sunt cu 2mm mai mari decat diametrul buloanelor;
Lungimea cordoanelor de sudura este egala cu conturul de suprapunere a pieselor.
Grosimea sudurilor va fi egala 0.7tmin; dar nu mai putin de 3mm.

EXTRAS MATERIALE PTR 1 ANSAMBLU				G/5	1	buc. necesare	
Positia	Dimensiunea	Otel	buc.	Lungime [mm]	Aria laterala [mp]	Greutate [kg]	
1001	PL10*70	S235JR	4	100	0	0	
1002	PL3*80	S235JR	2	80	0	0	
1004	PL8*80	S235JR	4	130	0	1	
1009	PL10*133	S235JR	4	182	0	1	
1010	PL10*133	S235JR	4	196	0	1	
1012	60*8	S235JR	8	140	0	1	
P/1	RHS80*4	S235JR	1	9050	3	86	
P/2	RHS80*4	S235JR	2	4743	1	44	
P/3	RHS50*4	S235JR	1	1336	0	8	
P/4	RHS50*4	S235JR	2	886	0	5	
P/5	RHS50*4	S235JR	2	428	0	2	
P/6	RHS50*4	S235JR	2	1610	0	9	
P/7	RHS50*4	S235JR	2	1323	0	8	
P/8	PL10*70	S235JR	4	200	0	1	
P/10	RHS80*4	S235JR	1	290	0	3	
Total					9	256	

Verificator					
Verificator/ Expert	Nume	Semnatura	Cerinta	REFERAT / EXPERTIZA / NR. / DATA	
S.C. A.G. PROIECT-S S.R.L. C.U.I. 17069804 , J02/2218/2004 B_dul. Stefan Augustin Dolnas, nr. 41. ap. 2, ARAD Tel: 0721740641			Beneficiar: COMUNA ZERIND prin Primar Simandi Alexandru	Proiect nr.: 08/2022	
SPECIFICATIE	NUME	SEMNATURA	SCARA	Titlu proiect:	
SEF PROIECT:	Arh. Popa Romeo		1:5	ETAJARE CLADIRE VESTIARE BAZA SPORTIVA Jud. Arad, Comuna ZERIND, satul ZERIND, CF 302562	
Proiectat:	Ing. Molnar Huba		DATA	Titlu planse:	
Desenat:	Ing. Molnar Huba		2022	GRINDA DE ZABRELE G/5	
				Faza: DTAC + PT	
				Plansa nr. M.13	